

## Addendum No. 1

Date: May 19, 2023

Solicitation Number: FY23-IFCON-07

Title: Coliseum Creek Stream Repair

Issued by: Katherine Osborne

Katherine.Osborne@charlottenc.gov

Bidders should acknowledge receipt of this addendum on the Execution of Bid Form. Failure to acknowledge receipt of this addendum may result in the bid not being considered.

## **Modifications to the Invitation to Bid:**

#	ITB Section # and Name	Page and Paragraph	Modification
1	INVITATION TO BID	Page 1	Last paragraph titled "BID FORM" is hereby deleted in its entirety and replaced with the following:
			Complete, sign and submit the forms on pages 1 through 8 in the "Itemized Bid Forms and Supplements" section by or before the due date and time.

## **Questions and Responses**

1. Question: Please provide clarification of Note 3 of Sheet 3 on the same sheet.

**Response:** Log cuts referred to in Note 3 on Sheet 3 of the construction drawings are

to be field determined by the Engineer, City Inspector, and Contractor and marked by non-toxic, utility marking spray paint for Contractor to use as

limits in performing the cuts.

2. Question: The Contract Manual states that surveying will be provided by the City but

note 4 requests the contractor stake out limits of disturbance. Please

clarify?

**Response:** The intent of Note 4 on Sheet 3 of the construction drawings is for the City

to survey and stake out limits of disturbance. The Engineer and City Inspector will meet with Contractor to confirm or adjust limits of

disturbance based on field inspection and Contractor input. Adjustments

will be made by Engineer and City Inspector only.

Addendum No. 1 Page 1



3. Question: Does the number of logs in the old structures balance with what we need

for the proposed or will we need an outside source for more logs?

Response: Existing logs have the potential to be reused if appropriately sized and

determined by the Engineer to be in good condition for reuse (i.e. free

from substantial rot and damage).

**4. Question:** Line item 10, Timber Mat, doesn't seem to be depicted on the plan

anywhere. Where will we use this?

Response: Temporary stream crossings are shown on Sheets 6 and 7 of the

Construction Drawings. Timber mats, Detail 4 on Sheet 8, may be alternatively used and paid for at these locations to limit disturbance to the channel, which will require restoration of the channel back to existing

conditions where stream crossing is performed.

**4.** Question: Since this is an "informal bid" does our own status as a SBE count?

**Response:** A City MWSBE may count the work it intends to perform, with its own current

workforces, towards the MWSBE Subcontracting Goals to the extent the requirements set forth in this Section are satisfied and the amount of the Construction Contract is under \$500,000. Please reference Part B Section

3.1 of the CBI Program Policy

**5. Question:** Please clarify Note 6 on Sheet 3 of the Construction Drawings

**Response:** Note 6 on Sheet 3 of the construction drawings should read that the City

will stake out the proposed alignment for Ditch E and location of last drop

prior to Reach E for field review by Engineer.

 <b>END OF</b>	<b>ADDENDUM</b>	NO. 1	

## **ATTACHMENTS**

Coliseum Creek Access Map

Addendum No. 1 Page 2



