



Addendum No. 2

Date: *May 24, 2023*

Solicitation Number: *FY23-IFCON-07*

Title: *Coliseum Creek Stream Repair*

Issued by: *Katherine Osborne*
Katherine.Osborne@charlottenc.gov

Bidders should acknowledge receipt of this addendum on the Execution of Bid Form. Failure to acknowledge receipt of this addendum may result in the bid not being considered.

Questions and Responses

- 1. Question:** In section 11 of the project manual, it is stated that the City will provide surveying. The plans note that the contractor is to stake out the LOD for field review by the engineer. Will the contractor need to provide survey for the LOD or will the City provide survey/stake out for the LOD?

Response: The City will provide all survey.
- 2. Question:** If we do not disturb areas designated to be worked in will we be required still to install coir matting?

Response: Build per plans.
- 3. Question:** We notice that we will need several trees to complete the project, where will these come from: and also plans indicate some to be 18" DBH and then on the special conditions they indicate 8 to 12" DBH?

Response: See SPSRWs for trees.
For log sill, use 8 to 12 inch trees.
For angled log riffle, use 18 to 24 inch trees.

. ----- **END OF ADDENDUM NO. 2** ----- .