
Addendum No. 4

Date: *April 21, 2023*

Solicitation Number: *FY23-ITBCON-20*

Title: *Sugar Creek WWTP Alkalinity Storage Replacement*

Issued by: *Katherine Osborne*
Katherine.Osborne@charlottenc.gov

Bidders should acknowledge receipt of this addendum on the Bid Form. Failure to acknowledge receipt of this addendum may result in the bid not being considered.

Clarifications:

1. Charlotte Water received one bid on April 18, 2023, at 2:00 p.m.
2. Storage tanks shall be designed to directly support the top entering vertical mixers as shown on the drawings. Separate bridge supports for mixers will not be allowed. Per paragraph 46 41 41-2.03F tank internal baffles shall be provided by the tank manufacturers at the dimensions requested by the mixer manufacturers and as coordinated by the Contractor.
3. In coordination with paragraph 46 41 41-2.03E, add an 8-inch nozzle for the top entering mixers to the tank nozzle tables of paragraphs 43 41 13-2.03B and 43 41 46-2.03J.
4. The nominal capacity of each storage tank is approximately 9,000 gallons. If tank structural constraints limit manufacturers in providing this capacity, the Owner will accept a tank with a nominal capacity of no less than 8,600 gallons with a diameter of no less than 13 feet. The height of the tank cannot exceed 8'-8" as listed in Section 43 41 46 to meet the minimum required clearance of 80 inches between the top of the tank and the roof bracing.

----- END OF ADDENDUM NO. 4 -----