

Project #:
Project Name:

ITEMIZED BID

BIDDER NAME: _____
PROJECT #: HC2023-1195
PROJECT NAME: Cross Charlotte Trail - Orr Road to Rocky River Road

SECTION 1: BID

<i>Item</i>	<i>Section</i>	<i>ITEM DESCRIPTION</i>	<i>Quantity</i>	<i>Unit</i>	<i>Unit Price</i>	<i>Amount</i>
1	800	Mobilization	1	LS		\$0.00
2	SP-01	Comprehensive Grading	1	LS		\$0.00
3	226	Undercut Excavation	356	CY		\$0.00
4	270	Geotextile for Soil Stabilization	1390	SY		\$0.00

Project #:
Project Name:

Item	Section	ITEM DESCRIPTION	Quantity	Unit	Unit Price	Amount
5	SP-02	Rock Removal	150	CY		\$0.00
6	SP-03	Select Material	106	TN		\$0.00
7	SP-08	Biaxial Geogrid	12620	SY		\$0.00
8	310	15" R.C. Pipe Culverts, Class III	144	LF		\$0.00
9	310	15" R.C. Pipe Culverts, Class IV	76	LF		\$0.00
10	310	18" R.C. Pipe Culverts, Class IV	24	LF		\$0.00
11	310	24" R.C. Pipe Culverts, Class III	128	LF		\$0.00
12	310	24" R.C. Pipe Culverts, Class IV	29	LF		\$0.00
13	310	36" R.C. Pipe Culverts, Class IV	29	LF		\$0.00
14	310	15" R.C. Flared End Section (CLDS 20.22)	3	EA		\$0.00
15	310	36" R.C. Flared End Section (CLDS 20.22)	1	EA		\$0.00
16	SPU-01	Relocate Existing Clean Out	9	EA		\$0.00
17	SPU-02	6" Sewer Manhole Outside Drop Assembly	5	LF		\$0.00
18	SPU-03	6" PVC Sewer Pipe, SDR 26	650	LF		\$0.00
19	520	Aggregate Base Course	4,658	TN		\$0.00
20	607	Milling Asphalt Pavement, 0.0" to 3.0"	105	SY		\$0.00
21	610	Asphalt Concrete Base Course, Type B 25.0C	220	TN		\$0.00
22	610	Asphalt Concrete Intermediate Course, Type I 1	50	TN		\$0.00
23	610	Asphalt Concrete Surface Course, Type S 9.5C	50	TN		\$0.00
24	610	Asphalt Concrete Surface Course, Type S 9.5B	1,120	TN		\$0.00
25	620	Asphalt Binder for Plant Mix	95	TN		\$0.00

Project #:
Project Name:

Division 00 - Procurement Contracting Requirements

<i>Item</i>	<i>Section</i>	<i>ITEM DESCRIPTION</i>	<i>Quantity</i>	<i>Unit</i>	<i>Unit Price</i>	<i>Amount</i>
26	SP-07R	6" Concrete Greenway (Fiber Reinforced)	2830	SY		\$0.00
27	801	Construction Surveying	1	LS		\$0.00
28	838	Endwalls	34	CY		\$0.00
29	840	Masonry Drainage Structures	2	EA		\$0.00
30	840	Frame with Grate (all types)	2	EA		\$0.00
31	846	2' 6" Concrete Curb and Gutter	1140	LF		\$0.00
32	848	4" Concrete Sidewalk or pad	223	SY		\$0.00
33	848	6" Concrete Driveways	410	SY		\$0.00
34	SP-06	6" Concrete Wheelchair Ramps	221	SY		\$0.00
35	858	Adjustment of Manholes	1	EA		\$0.00
36	858	Adjust Water Valve	2	EA		\$0.00
37	858	Adjustment of Meter Boxes or Valve Boxes	2	EA		\$0.00
38	SPU-04	Relocate Existing Fire Hydrant	1	EA		\$0.00
39	876	Riprap (Class A, Class B, Class I & Class II)	248	TN		\$0.00
40	876	Geotextile for Drainage	186	SY		\$0.00
41	SP-12	Fence, 6' Chain Link	1016	LF		\$0.00
42	SP-12	Fence, 6' Chain Link Double Gate	1	EA		\$0.00
43	SP-04	Traffic Control	1	LS		\$0.00
44	901	Contractor Furnished, Type E Sign	40	SF		\$0.00
45	904	Sign Erection, Type E	4	EA		\$0.00

Item	Section	ITEM DESCRIPTION	Quantity	Unit	Unit Price	Amount
46	1205	Thermoplastic Pavement Marking Lines, 8", 120	700	LF		\$0.00
47	1205	Thermoplastic Pavement Marking Lines, 6", 120	25	LF		\$0.00
48	1205	Thermoplastic Pavement Marking Lines, 4", 120	1336	LF		\$0.00
49	1205	Thermoplastic Pavement Marking Lines, 24", 120	28	LF		\$0.00
50	1205	Thermoplastic Pavement Marking Symbols, 120	14	EA		\$0.00
51	SP-10	Green Thermoplastic	120	SF		\$0.00
52	SP-09R	Permanent Bollard,Owner Provided, Contractor	8	EA		\$0.00
53	SP-09R	Collapsible Bollard,Owner Provided, Contractor	1	LS		\$0.00
54	SP-05	Erosion Control	1	LS		\$0.00
55	SP-13	Precast Gravity Retaining Walls	4700	SF		\$0.00
56	SP-14	Wall, Gravity Retaining (Cast in Place)	20	CY		\$0.00
57	SP-15	Soldier Pile Retaining Walls	3830	SF		\$0.00
58	SP-11R	Safety Rail, Metal	760	LF		\$0.00
59	SP-16	Concrete Swale Bridge	3	EA		\$0.00
60	SP-17	Structure #1 (Timber Boardwalk w/ Concrete D	1	LS		\$0.00
61	SP-17	Structure #2 (Timber Boardwalk w/ Concrete D	1	LS		\$0.00
62	SP-17	Structure #3 (Timber Boardwalk w/ Concrete D	1	LS		\$0.00
63	SP-17	Structure #4 (Timber Boardwalk w/ Concrete D	1	LS		\$0.00
64	SP-17	Structure #5 (Timber Boardwalk w/ Concrete D	1	LS		\$0.00
65	SP-17	Structure #6 (Timber Boardwalk w/ Concrete D	1	LS		\$0.00
66	SP-17	Overlook	1	LS		\$0.00

Project #:
Project Name:

<i>Item</i>	<i>Section</i>	<i>ITEM DESCRIPTION</i>	<i>Quantity</i>	<i>Unit</i>	<i>Unit Price</i>	<i>Amount</i>
67	SP-18	Bench (Owner Provided, Contractor-Installed)	4	EA		\$0.00
68	SP-19	Trash Receptacle (Owner Provided, Contractor-	3	EA		\$0.00
69	SP-20	Landscape Boulders (Owner Provided, Contract	9	EA		\$0.00
70	SP-23	Exterior Planting	1	LS		\$0.00
Subtotal						\$0.00
				<u>10.0%</u>	Contingency	\$0.00
Total Bid						\$0.00

Do not include any North Carolina Sales and Use Tax that qualifies as Eligible Taxes per Section 00 70 00, Subsection 2.17 "Sales and Use Tax".