

| <i>CIC</i> | <i>Section</i> | <i>Item Description</i>  | <i>Qty</i> | <i>Unit</i> | <i>Recommended<br/>minimum Unit Price</i> | <i>Notes</i>                            |
|------------|----------------|--|------------|-------------|---|---|
| 80135.000  | SP             | Select Material  | 1,200      | TN          | \$ 40.00                                  |   |
| 10226.101  | 226            | Undercut Excavation  | 200        | CY          | \$ 60.00                                  |   |
| 10270.000  | 270            | Geotextile for Soil Stabilization                                  | 500        | SY          | \$ 8.00                                   |   |
| 10300.000  | 300            | Foundation Conditioning Material, Minor Structures                 | 100        | TN          | \$ 50.00                                  |   |
| 10300.100  | 300            | Foundation Conditioning Geotextile                                 | 240        | SY          | \$ 8.00                                   |   |
| 10310.003  | 310            | 15" R.C. Pipe Culverts, Class III                                  | 24         | LF          | \$ 120.00                                 |   |
| 10310.006  | 310            | 18" R.C. Pipe Culverts, Class III                                  | 375        | LF          | \$ 135.00                                 |   |
| 10310.009  | 310            | 24" R.C. Pipe Culverts, Class III                                  | 16         | LF          | \$ 160.00                                 |   |
| 10310.012  | 310            | 30" R.C. Pipe Culverts, Class III                                  | 93         | LF          | \$ 220.00                                 |   |
| 10310.015  | 310            | 36" R.C. Pipe Culverts, Class III                                  | 201        | LF          | \$ 250.00                                 |   |
| 10520.000  | 520            | Aggregate Base Course  | 185        | TN          | \$ 50.00                                  |   |
| 10607.059  | 607            | Milling Asphalt Pavement, 0.0" to 3.0"                             | 5,340      | SY          | \$ 8.00                                   |   |
| 10610.051  | 610            | Asphalt Concrete Base Course, Type B 25.0C                         | 240        | TN          | \$ 125.00                                 | For much larger quantities, use \$90/TN |
| 10610.201  | 610            | Asphalt Concrete Intermediate Course, Type I 19.0C                 | 170        | TN          | \$ 125.00                                 | For much larger quantities, use \$90/TN |
| 10610.451  | 610            | Asphalt Concrete Surface Course, Type S 9.5C                       | 590        | TN          | \$ 125.00                                 | For much larger quantities, use \$90/TN |
| 10620.000  | 620            | Asphalt Binder for Plant Mix                                       | 70         | TN          | \$ 900.00                                 |   |
| 10840.022  | 840            | Masonry Drainage Structures  | 17         | EA          | \$ 4,000.00                               |   |
| 10840.101  | 840            | Masonry Drainage Structures  | 45         | LF          | \$ 500.00                                 |   |
| 10840.355  | 840            | Frame with Grate (all types)                                       | 11         | EA          | \$ 1,000.00                               |   |
| 10840.053  | 840            | Manhole Frame and Cover, NCDOT Std 840.54                          | 8          | EA          | \$ 750.00                                 |   |
| 10846.052  | 846            | 2' 6" Concrete Curb and Gutter                                     | 1,560      | LF          | \$ 35.00                                  |   |
| 10848.000  | 848            | 4 " Concrete Sidewalk or pad                                       | 710        | SY          | \$ 55.00                                  |   |
| 10848.051  | 848            | 6" Concrete Driveways  | 560        | SY          | \$ 100.00                                 |   |
| 81062.000  | SP             | Pedestrian Refuge Island (Pass-Thru)                               | 99         | SY          | \$ 150.00                                 |   |
| 80218.000  | SP             | 6" Concrete Wheelchair Ramps                                       | 67         | SY          | \$ 250.00                                 |   |
| 10852.001  | 852            | 5" Monolithic Concrete Islands                                     | 230        | SY          | \$ 125.00                                 |   |
| 10852.001  | 876            | Geotextile for Drainage  | 2,300      | SY          | \$ 5.00                                   |   |
| 81006.000  | SP             | Wall, Precast Modular Block Retaining                              | 270        | SF          | \$ 75.00                                  |   |
| 80010.000  | SP             | Safety Rail, Metal CLDS 50.04                                      | 60         | LF          | \$ 90.00                                  |   |
| 11205.052  | 1205           | Thermoplastic Pavement Marking Lines, 4", 90 mils                  | 3,800      | LF          | \$ 2.00                                   |   |
| 11205.039  | 1205           | Thermoplastic Pavement Marking Lines, 6", 90 mils                  | 1,000      | LF          | \$ 4.00                                   |   |
| 11205.026  | 1205           | Thermoplastic Pavement Marking Lines, 8", 90 mils                  | 1,950      | LF          | \$ 6.00                                   |   |
| 11205.036  | 1205           | Thermoplastic Pavement Marking Lines, 12", 90 mils                 | 500        | LF          | \$ 10.00                                  |   |
| 11205.082  | 1205           | Thermoplastic Pavement Marking Lines, 24", 90 mils                 | 200        | LF          | \$ 20.00                                  |   |
| 11205.185  | 1205           | Thermoplastic Pavement Marking Symbols, Left-Turn Arrow            | 15         | EA          | \$ 200.00                                 |   |
| 11205.183  | 1205           | Thermoplastic Pavement Marking Symbols, (Bicycle) 120 mils:        | 15         | EA          | \$ 300.00                                 |   |
| 11205.184  | 1205           | Thermoplastic Pavement Marking Symbols, (Bicycle Arrow), 120 mils: | 12         | EA          | \$ 200.00                                 |   |
| 81874.000  | SP             | Green Thermoplastic  | 2,700      | SF          | \$ 20.00                                  |   |
| 81548.000  | SP             | Reflective Paddles   | 21         | EA          | \$ 450.00                                 |   |
| 11715.004  | 1715           | Unpaved Trenching (2-2" SCH80)                                     | 450        | LF          | \$ 30.00                                  |   |
| 11716.001  | 1716           | Junction Box (13"x24"x12" PC, TRAFFIC SIGNAL logo)                 | 9          | EA          | \$ 1,500.00                               |   |
| 81782.000  | SP             | Concrete Foundation for 10 foot Metal Base/Pole/Pedestrian Signal  | 9          | EA          | \$ 1,500.00                               |   |