



**MECKLENBURG COUNTY**  
**Land Use & Environmental Services Agency**

**MEMORANDUM**

To: Charlotte-Mecklenburg Planning Commission  
From: LUESA, Mecklenburg County  
Date: 8.31.21  
Subject: Rezoning Petition Comments

Charlotte-Mecklenburg Planning Commission  
600 East Fourth Street Charlotte, North Carolina 28202

Mecklenburg County has reviewed the City of Charlotte rezoning petition below to identify regulatory requirements of the petitioner; inform the petitioner, planning staff, and other affected parties of such regulatory requirements; and identify potential effects on, and impacts from, nearby properties.

<b><u>Petitioner Information:</u></b> gina La Blanc LONG COVE INVESTMENT GROUP LLC 13000 S TRYON ST UNIT F-221 CHARLOTTE, NC, 28278 Home Phone: 14075209731 gina@locktrust.com	<b><u>Parcel GIS ID(s):</u></b> 19934202
---	---

**2021-101: Long Cove Club & Marina Rezoning**

*Air Quality Comments:* No comment on this rezoning petition.

*Ground Water Services Comments:* Information from property records does not indicate the current use of oil heat, but since records indicate that the structure was built in 1978 and because a marina has operated at the property, the property may contain underground or above ground petroleum storage tanks. Any existing tank and its contents should be removed, following applicable NCDEQ guidance, prior to any demolition or grading activity.

Records available to GWS indicate a Transient Public Well is registered at this property. If water supply wells exist at this property, then the wells should be protected during site development by flagging and

fencing or be permanently abandoned in accordance with NC Division of Water Resources Public Water Regulations prior to site development commencing.

Records available to GWS indicate a septic system or systems are registered at this property. No regulations govern the abandonment of septic systems; however, if a septic system exists on this property GWS does recommend that septic tanks be pumped by a NC Licensed Septic Hauler to remove any residual contents and then crushed and backfilled. This recommendation is made because improperly abandoned septic tanks may not be able to support the weight of vehicular traffic, structural foundations or people posing a safety hazard.

*Storm Water Services Comments:* A Floodplain Development permit must be obtained documenting compliance with the City of Charlotte Floodplain Regulations for all development occurring in the floodplain. In addition, staff recommend any structures proposed within the Community Special Flood Hazard Area be constructed to a Flood Protection Elevation equal to the Community Base Flood Elevation plus two (2) feet of freeboard based upon recent analyses of the future floodplains supported by the Storm Water Advisory Committee.

*Solid Waste Comments:* No comments

**Department Contacts:**

Petitioners seeking to address individual comments and issues may follow up with the following Mecklenburg County staff:

*Air Quality Comments:* PJ McKenzie - (paul.mckenzie@mecklenburgcountync.gov)

*Ground Water Services:* Shawna Caldwell - (shawna.caldwell@mecklenburgcountync.gov)

*Storm Water Services:* Myrette Stephen - (myrette.stephen@mecklenburgcountync.gov)

*Solid Waste Comments:* Joe Hack - (joe.hack@mecklenburgcountync.gov)

Additionally, please CC Dylan Kirk, (dylan.kirk@mecklenburgcountync.gov) on all communications to individual departments.

**MCAQ Scope of Review:**

Mecklenburg County Air Quality (MCAQ) has reviewed the petitions with regard to air quality regulations for stationary sources and demolition and/or renovation of structures (e.g. National Emission Standards for Hazardous Air Pollutants for asbestos). Comments may also be made regarding incompatible land uses, sources of Toxic Air Pollutants, proximity to Risk Management Plan facilities, and proximity to known nuisance conditions or sensitive populations. MCAQ has conducted the review based on information submitted by the petitioner, review of aerial photographs (as available through the Mecklenburg County Polaris system), review of the "Air Pollution Facility Information Online" database available from the MCAQ website, and review of Mecklenburg County Health Department records. The review is cursory based on limited information provided within petition applications and site plans.