

Recommended Alternative Improvements Summary Meeting



Water Oak Storm Drainage Improvement Project

Phalanx #31 Masonic Lodge
December 5, 2013



Introduction of Staff

- **Charlotte-Mecklenburg Storm Water Services (CMSWS)**
 - Adrian Cardenas, PE – Project Manager
 - Phone - 704-336-4682
 - E-mail - acardenas@charlottenc.gov
 - Doug Lozner, PE – Watershed Area Manager
- **Mulkey Engineers & Consultants**
 - David Bocker, PE – Project Manager
 - Andrea Hayden, PE – Project Engineer
 - J.R. Hopson, EI – Hydraulic Designer

Housekeeping Items

- Sign-In
- Agenda, and other handouts
- Customer Service Comment Cards
- Question and Answer period after presentation

Meeting Purpose and Agenda

- Purpose
 - Provide a summary of the Recommended Alternative Improvements
 - Request input from property owners/residents on the Recommended Alternative Improvements
- Agenda
 - Project Progress and Current Status
 - Recommended Alternative Improvements Summary
 - Future project milestones - path forward
 - General Questions and Comments
 - Small group break-out sessions

Why the Water Oak Storm Drainage Improvements Project (SDIP) was chosen as an Engineering project

- **Requests for Service from Property Owners (115 request for service within watershed)**
 - **Inadequate Infrastructure**
 - Road flooding
 - Structure flooding (House, buildings, sheds, etc.)
 - **Deteriorating Infrastructure**
 - Old culverts, pipes, inlets
 - Sink holes
 - Erosion, blockages in streams
- **CMSWS watershed ranking**
- **Larger watershed-wide issues that cannot be managed by spot repairs or without potentially impacting downstream properties**

What we need from you

- **Feedback on the Recommended Alternative Improvements**
- **Support for the project's future phases**

Storm Drainage Improvement Project Phases

PLANNING (Typically 16 to 23 months)

- *Existing Conditions Analysis – Finding the Problems (Started early 2012)*
- *Alternative Analysis – Finding the Solutions*

DESIGN (Typically 21 to 34 months)

- *Designing the Solutions*

PERMITTING (Typically 3 to 9 months, but usually overlaps the design phase)

EASEMENT ACQUISITION (Typically 12 months, overlaps with the design phase)

BID (Typically 4 to 5 months)

CONSTRUCTION (3 months to over 2 years)

Planning Phase

(began February 2012)

- **Survey, Public Input & Questionnaires**
 - Original questionnaires were sent out in December of 2011
- **Existing Conditions Analysis**
 - 1st Public Meeting – Held on January 24, 2013
- **City Design Standards Alternative**
- **Alternative Analyses**
- **Recommended Alternative**
 - 2nd Public Meeting – December 5, 2013

EVALUATING ALTERNATIVES

Coming up with the “BEST” solutions



1. Public Safety

2. Private Property
Impact



3. Public Cost

EVALUATING ALTERNATIVES

Types of Alternatives Considered


- **Replacement of failing pipes**
- **Different culvert and pipe sizes**
- **Different culvert/pipe shapes and materials**
- **Additional pipes and inlets**
- **New Alignments**
- **Detaining Water to Reduce Flow**
- **Stream Stabilization**
- **Changing stream profiles**

Water Oak Storm Drainage Improvement Project

Recommended Alternative Improvements




Project Area Map




Existing Conditions Results East Outfall:

- Linda Lane and Sharon Amity Road experience street flooding during 100-yr storm
- Eighteen (18) buildings including storage buildings experience flooding




Recommended Alternative Improvements East Outfall:

- System upgrade & realignment at Hartness Avenue / Water Oak Road to Judith Court
- System upgrade on existing alignment from Bridlepath Lane to Linda Lane to Brantham Court to Sharon Amity Road to Regency Apartment Complex




Existing Conditions Results West Outfall:

- Sharon Amity Road (Ex. 30" pipe crossing) experiences street flooding during 10-yr storm
- No building flooding




Recommended Alternative Improvements West Outfall:

- Realignment of system at Water Oak Road / Queen Charlotte Court intersection
- Addition of inlets on Linda Lane
- Upgrade of Sharon Amity Road (Ex. 30" pipe crossing) to 2 pipes (1 – 48" & 1 – 42")
- Realignment of system at Water Oak Road / Sharon Amity Road intersection to tie to proposed system at Regency Apartments



Existing Conditions Results Central Outfall:


- Stafford Circle, Emory Lane, and Addison Drive experience street flooding during 10-yr storm
- One building including storage buildings experiences flooding related to the Water Oak system
- Contains FEMA regulated floodplain (McMullen Creek Tributary)



Recommended Alternative Improvements

Central Outfall:

- System upgrade & realignment at Stafford Circle
- Upgrade & realignment of Emory Lane pipe crossing from 2 – 42" to 2 – 7'x5' box culverts
- System upgrade & realignment on Addison Drive



Storm Drainage Improvement Project Phases

PLANNING (Typically 16 to 23 months)

- *Existing Conditions Analysis – Finding the Problems (Started early 2012)*
- ***Alternative Analysis – Finding the Solutions***

DESIGN (Typically 21 to 34 months)

- *Designing the Solutions*

PERMITTING (Typically 3 to 9 months, but usually overlaps the design phase)

EASEMENT ACQUISITION (Typically 12 months, overlaps with the design phase)

BID (Typically 4 to 5 months)

CONSTRUCTION (Approximately 12 to 24 months)

Path Forward

- Additional information obtained during this meeting will be considered and incorporated into the Selected Alternative Improvements, where feasible.
- Design of the Selected Alternative Improvements.
- CMSWS will then hold a third public meeting to present and obtain feedback on the preliminary design.

Wrapping Up

- Please remember to sign-in and fill out a customer service card
- The City and our consultant will stay here to answer any specific questions you may have
- General Discussion

Thank you for coming to the meeting!
Special thank you to the Masonic Lodge
for providing their facilities to our community.