

1'-6"

1'-6"

NOTES:

1. THIS DETAIL CAN BE USED AT ROUNDABOUTS ON ALL NCDOT AND CITY OF CHARLOTTE STREETS WITH PRIOR NCDOT AND CITY APPROVAL.

CONCRETE -

(TYP.)

2'-6" CURB AND GUTTER

PER CLDS 10.17A

SIDEWALK PER CLDS 10.22

- 2. WIDTH OF TRUCK APRON AND CIRCULATORY ROADWAY TRAVEL LANE SHALL BE IN ACCORDANCE TO CURRENT "NCHRP 672 ROUNDABOUTS: AN INFORMATION GUIDE" (CURRENT EDITION).
- 3. TRUCK APRON SHALL BE CONCRETE AND STAMPED WITH A BRICK PATTERN.
- 4. CONCRETE SHALL BE NATURALLY COLORED.

2'-6"

- 6. ENSURE POSITIVE DRAINAGE THROUGHOUT THE APRON. AVOID STORM DRAINAGE STRUCTURES WITHIN THE MOUNTABLE CURB AND GUTTER.
- 7. INSTALL "SPILL" CURB AND GUTTER BETWEEN THE TRUCK APRON AND THE CENTER OF THE ROUNDABOUT. THE GUTTER SPILL SLOPE MUST MATCH THE SLOPE OF THE ADJACENT TRUCK APRON.

NOT TO SCALE

2:1 CUT MAX.

3:1 FILL MAX.



CITY OF CHARLOTTE LAND DEVELOPMENT STANDARDS INCLUDES CHARLOTTE ETJ

TRUCK APRON AT ROUNDABOUT

10.45B